



**NOTES:**

1. STABLE TRENCH: UNDISTURBED SOIL OR COMPACTED TO 95% RC UNSTABLE TRENCH: INSTALL ROCK BALLAST AND GEOTEXTILE FILTER FABRIC AS SHOWN
2. CONTRACTOR SHALL VERIFY REQUIREMENTS WITH GOVERNING AGENCY (CITY OR COUNTY)

**NAPA SANITATION DISTRICT**



TITLE  
**RECYCLED WATER MAIN  
 TRENCH SECTION**

DATE: **JAN 2016**  
 CHECKED BY: **AD**  
 APPROVED BY: **TH**  
 SCALE: **NONE**

DRAWING NO.  
**RW-4**