



NOTES:

1. AFTER MANHOLE BASE HAS CURED ENOUGH TO SUPPORT THE WEIGHT OF THE MANHOLE SECTIONS, RAM-NEK SHALL BE PLACED IN THE GROOVE IN THE MANHOLE BASE AND THE BARREL SECTION SET IN PLACE.
2. THE JOINT BETWEEN THE BARREL SECTION AND MANHOLE BASE SHALL HAVE 6" TO 8" ALLCRETE OR EQUAL OUTSIDE THE JOINT PRIOR TO BACKFILL.
3. WRAP ALL EXTERIOR JOINTS WITH WRAPIDSEAL PRIOR TO BACKFILLING.
4. THE REMAINDER OF THE MANHOLE SHALL BE STACKED IN ACCORDANCE WITH SS-10.
5. SEE GENERAL NOTES ON SS-9A FOR ADDITIONAL REQUIREMENTS.
6. STRETCHING OF RAM-NEK IS PROHIBITED.

NAPA SANITATION DISTRICT



TITLE

**TYPICAL MANHOLE
USING
IMPRESSION RING**

DATE: **JAN 2016**

CHECKED BY: **AD**

APPROVED BY: **TH**

SCALE: **NONE**

DRAWING NO.

SS-11