

STANDARD SPECIFICATIONS

TABLE OF CONTENTS

VOLUME I GENERAL CONDITIONS

SECTION 1 - INTRODUCTION **1**

 1.01 INTRODUCTION 1

SECTION 2 - DEFINITIONS AND TERMS **2**

 2.01 DEFINITIONS AND TERMS 2

 2.02 ABBREVIATIONS 5

 2.03 PIPE TYPES 5

SECTION 3 - SCOPE OF WORK **6**

 3.01 SCOPE 6

 3.02 GUARANTEE OF WORK 6

 3.03 INDEMNIFICATION 6

 3.04 SAFETY 7

 3.05 PRESERVATION OF PROPERTY 7

 3.06 TRADE NAMES AND ALTERNATIVES 8

SECTION 4 - SITE PREPARATION **9**

 4.01 CONTAMINATED MATERIALS 9

SECTION 5 - SITE CLEANUP **10**

 5.01 SITE CLEANUP 10

SECTION 6 - PAVING REPLACEMENT **11**

 6.01 DEFINITION 11

 6.02 PAVING IN PUBLIC RIGHTS-OF-WAY OR PUBLIC UTILITY EASEMENT 11

 6.03 PAVING IN NAPA SANITATION DISTRICT EASEMENTS AND IN PRIVATE PROPERTY 11

 6.04 ALL-WEATHER ACCESS 11

SECTION 7 - REQUIREMENTS FOR ISSUANCE OF CONSTRUCTION PERMITS **12**

 7.01 PROPERTY TO BE SERVED BY DISTRICT 12

 7.02 LICENSE REQUIREMENTS 12

 7.03 BOND/DEPOSIT REQUIREMENTS 12

 7.04 FEES AND CHARGES 12

 7.05 SUBMISSION OF DATA FOR MAIN SEWERS AND RECYCLED WATER MAINS 12

 7.06 SUBMISSION OF DATA FOR PUBLIC LATERALS AND CONNECTIONS TO RECYCLED
 WATER MAINS 15

 7.07 SUBMISSION OF DATA FOR PRIVATE LATERALS AND PRIVATE RECYCLED WATER
 SYSTEMS 15

 7.08 WASTE DISCHARGE REPORT/PERMIT 17

7.09 PRIVATE EASEMENT REQUIREMENTS.....	17
7.10 ENCROACHMENT PERMIT.....	18
7.11 MINIMUM REQUIREMENTS FOR DIGITAL SUBMITTAL.....	18
SECTION 8- MISCELLANEOUS SEWER AND RECYCLED WATER REQUIREMENTS	19
8.01 REPAIR OR RELOCATION OF EXISTING MAIN SEWER, RECYCLED WATER MAIN, OR APPURTENANCES.....	19
8.02 REPAIR, RELOCATION OF OR CONNECTION TO EXISTING PRIVATE LATERALS AND PRIVATE RECYCLED WATER SYSTEMS.....	19
8.03 USE OF EXISTING LATERAL SEWERS AND RECYCLED WATER PIPES.....	19
8.04 ABANDONMENTS.....	19
8.05 NUMBER OF PRIVATE LATERALS REQUIRED.....	20
8.06 WORK IN PAVED AREAS.....	20
SECTION 9 - REQUIREMENTS PRIOR TO START OF CONSTRUCTION	21
9.01 PERMIT.....	21
9.02 STAKING AND CUT SHEETS.....	21
9.03 INSPECTION.....	21
SECTION 10 - APPROVAL AND ACCEPTANCE OF CONSTRUCTION	23
10.01 MAIN SEWERS AND RECYCLED WATER MAINS.....	23
10.02 PUBLIC LATERALS AND CONNECTIONS TO RECYCLED WATER MAINS.....	23
10.03 PRIVATE SEWERS.....	23
10.04 PAYMENT.....	23

VOLUME II SANITARY SEWER

SECTION 1 - SEWER PIPE LINES	1
1.01 SEWER CONSTRUCTION MATERIALS.....	1
1.02 PIPE MATERIALS.....	1
1.03 PIPE COUPLINGS.....	8
1.04 MAIN CONNECTIONS.....	8
1.05 EMBEDMENT.....	9
1.06 STAINLESS STEEL BANDS.....	9
SECTION 2 - PORTLAND CEMENT CONCRETE AND MORTAR	10
2.01 CONCRETE.....	10
2.02 MORTAR AND GROUT.....	11
SECTION 3 - SEWER PIPE AND STRUCTURE INSTALLATION	13
3.01 SEWER PIPE INSTALLATION.....	13
3.02 SPLICE.....	17
3.03 MANHOLE.....	17
3.04 RISER (Main Sewer Only).....	22

3.05 CLEANOUT TO GRADE (Private Lateral Only).....	22
3.06 TWO-WAY CLEANOUT TO GRADE (Private Lateral Only).....	22
3.07 TEST WYE (Private Lateral Only)	23
3.08 SEWER THROUGH CASING	23
3.09 SEWER THROUGH BORE	24
3.10 REHABILITATION OF PRIVATE SEWERS USING PIPE-BURSTING.....	25
3.11 CURED IN PLACE PIPE (CIPP) LINING.....	27
SECTION 4 - EXCAVATION	32
4.01 DEFINITION	32
4.02 OPEN TRENCHING	32
SECTION 5 - TRENCH BACKFILLING	36
5.01 TRENCH BACKFILLING	36
5.02 PIPE FOUNDATION - (If Required by Engineer).....	36
5.03 GEOTEXTILE FILTER FABRIC.....	36
5.04 PIPE EMBEDMENT.....	37
5.05 TRENCH BACKFILL MATERIAL.....	38
SECTION 6 - MISCELLANEOUS REQUIREMENTS	40
6.01 INSPECTION.....	40
6.02 ALTERATIONS	40
6.03 DEFECTIVE WORK AND/OR MATERIALS	40
6.04 MANHOLE PROTECTION	40
6.05 USE OF EXISTING LATERAL SEWERS.....	41
6.06 PUBLIC (STREET) LATERAL MARKING.....	41
6.07 TRACER WIRE AND MARKER TAPE.....	41
6.08 MANHOLE MARKING	42
6.09 REPAIR OF DAMAGED SEWERS AND OTHER UTILITIES.....	42
6.10 ABANDONMENTS.....	42
6.11 GREASE AND OIL COLLECTION SYSTEMS	44
6.12 OUTDOOR SINK REQUIREMENTS.....	46
6.13 TRASH ENCLOSURE DRAIN REQUIREMENTS.....	47
6.14 CAR WASH REQUIREMENTS.....	48
6.15 POOL AND SPA REQUIREMENTS.....	48
6.16 WINTERIZING SANITARY SEWER SYSTEM DURING CONSTRUCTION.....	48
SECTION 7 – TESTING	49
7.01 TESTING MAIN SEWERS	49
7.02 TESTING PRIVATE AND PUBLIC SEWER LATERALS	52
7.03 TESTING PRESSURE SEWERS	53
7.04 MANHOLE VACUUM TESTING.....	53
7.05 ORDER OF WORK	54
SECTION 8 - TELEVISION INSPECTION	55
8.01 TELEVISION INSPECTION.....	55

SECTION 9 - CLEANING	57
9.01 CLEANING.....	57
SECTION 10 - DESIGN AND POLICY STANDARDS FOR MAIN SEWERS AND PUBLIC LATERAL	58
10.01 PIPE MATERIALS.....	58
10.02 PIPE MATERIAL CHANGES.....	58
10.03 SIZE AND SLOPE	58
10.04 MAIN SIZING CRITERIA.....	59
10.05 ALIGNMENT	59
10.06 CROSS CONNECTION.....	59
10.07 GRADE	59
10.08 GRADE STAKES	60
10.09 DESIGN DEPTH	60
10.10 MINIMUM PIPE COVER.....	60
10.11 TRENCH INTERSECTIONS.....	60
10.12 HORIZONTAL AND VERTICAL CLEARANCE REQUIREMENTS	60
10.13 WATER MAIN SEPARATION.....	61
10.14 CROSSING STORM DRAINS.....	65
10.15 STRUCTURE LOCATIONS	65
10.16 MAIN LOCATIONS	65
10.17 IN AND OUT ELEVATIONS AT MANHOLES	65
10.18 MAXIMUM DEFLECTION AT MANHOLES	65
10.19 MANHOLE RIM ELEVATION.....	65
10.20 CONNECTION TO EXISTING MANHOLE.....	66
10.21 CONNECTIONS BETWEEN MAIN SEWERS.....	66
10.22 CONNECTION BETWEEN PUBLIC AND PRIVATE LATERAL.....	66
10.23 DROP MANHOLES	66
10.24 BOLT-DOWN MANHOLES.....	66
10.25 EASEMENT ALL-WEATHER ACCESS REQUIREMENTS	66
10.26 EASEMENT ACCESS REQUIREMENTS	66
10.27 EXTENT OF SEWER MAIN IMPROVEMENTS.....	67
10.28 PUBLIC LATERAL CONNECTIONS TO EXISTING MAIN OR NEW MAIN	67
SECTION 11 - DESIGN AND POLICY STANDARDS FOR PRIVATE LATERALS	69
11.01 SIZE AND SLOPE	69
11.02 PIPE MATERIALS.....	69
11.03 ALIGNMENT	69
11.04 GRADE	69
11.05 GRADE STAKES	69
11.06 CURB MARKING	70
11.07 CONNECTION TO PUBLIC LATERAL	70
11.08 CONNECTION TO EXISTING PRIVATE SEWER.....	70
11.09 CONNECTION TO BUILDING DRAIN (PLUMBING KICK-OUT)	70
11.10 CLEARANCES	71

11.11 SEWER UNDER OR NEAR STRUCTURES.....	71
11.12 MINIMUM PIPE COVER.....	71
11.13 TRENCH INTERSECTIONS.....	71
11.14 HORIZONTAL UTILITY CLEARANCE.....	72
11.15 STRUCTURE TYPE AND LOCATION.....	72
11.16 OVERFLOW DEVICES.....	72
11.17 NUMBER OF PRIVATE SEWERS REQUIRED.....	72
11.18 PRIVATE PUMPING STATIONS.....	73
SECTION 12 - DESIGN AND POLICY STANDARDS FOR PRIVATE MAINS	74
12.01 GENERAL.....	74
SECTION 13 – PUMP STATIONS	75
13.01 PUMP STATIONS.....	75
13.02 PACKAGED PUMP STATIONS.....	82
13.03 PRIVATE LIFT STATIONS.....	86

SANITARY SEWER DETAILS

- SS-1 – Sanitary Sewer Cleanout
- SS-2 – Standard Residential Public Lateral for New Construction
- SS-3 –Sewer Lateral Crossing Above Utility, No Conflict in Grade
- SS-4 –Sewer Lateral Crossing Below Utility, No Conflict in Grade
- SS-5 – Simple Sewer Lateral Break with Conflict in Grade
- SS-6 – Sewer Lateral Layout 1
- SS-7 – Sewer Lateral Layout 2
- SS-8 – Drop Type Manhole
- SS-9 – Standard Pre-Fab Manhole (Sheet 1)
- SS-9A – Standard Pre-Fab Manhole (Sheet 2)
- SS-10 – Barrel Section Joints for Standard Pre-Fab Manhole
- SS-11 – Typical Manhole Using Impression Ring
- SS-12 – Pre-Cast Concrete 48”x24” Reducer Slab for Manholes
- SS-13 – Typical Method for Setting Appurtenances
- SS-14 – Standard 24” Manhole Frame and Cover
- SS-15 – Bolt-Down 24” Manhole Frame and Cover
- SS-16 – 36” Diameter Manhole Frame and Cover
- SS-17 – Typical Installation Irrigation “Subtraction” Meter
- SS-18 – Standard Casing Installation
- SS-19 – Redwood Check Dam
- SS-20 – Trench Dams
- SS-21 – Earth Trench Dam
- SS-22 – Two Stage Grease Interceptor
- SS-23 – Grease Interceptor Sampling Box
- SS-24 – Standard Trench Section

- SS-25 – Standard Tracer Wire Installation Detail
- SS-26 – Abandoned Pipe Plug
- SS-27 – Abandoned Manhole
- SS-28 – Standard Flush Hole for 6” and 8” Sanitary Sewer Mains
- SS-29 – Standard Trench Section for Private Sewer Lateral

VOLUME III RECYCLED WATER

SECTION 1 - RECYCLED WATER MAINS – GENERAL	1
1.01 RECYCLED WATER MAINS – GENERAL	1
1.02 RESTRAINED JOINTS	2
1.03 THRUST BLOCKS	2
1.04 MATERIALS	2
1.05 PRESSURE	5
SECTION 2 - CONNECTION TO AN EXISTING PUBLIC RECYCLED WATER MAIN	6
2.01 CONNECTIONS	6
SECTION 3 - ALIGNMENT	7
3.01 ALIGNMENT CRITERIA	7
3.02 MAIN SIZING CRITERIA	8
3.03 MIMIMUM MAIN/LATERAL COVER	8
SECTION 4 - RECYCLED WATER VALVING	10
4.01 RECYCLED WATER VALVING	10
4.02 SPECIALTY VALVES AND RECYCLED WATER SAMPLING STATIONS	11
SECTION 5 - HYDROSTATIC TEST	13
5.01 TESTING	13
SECTION 6 - SERVICE LATERALS AND METERS FOR IRRIGATION SERVICE	15
6.01 SERVICE LATERALS	15
SECTION 7 - BACKFLOW DEVICES	18
7.01 BACKFLOW DEVICES	18
SECTION 8 - SPECIAL CONDITIONS FOR DELINEATED FAULT ZONES	19
8.01 SPECIAL CONDITIONS	19
SECTION 9 - ABANDONMENT OF RECYCLED WATER MAINS AND SERVICES	20
9.01 ABANDONMENT OF RECYCLED WATER MAINS AND SERVICES	20
SECTION 10 - ON-SITE DESIGN STANDARDS	21
10.01 ON-SITE DESIGN STANDARDS	21

RECYCLED WATER DETAILS

- RW-1 – Concrete Anchor Blocks for Vertical Bends
- RW-2 – Concrete Thrust Blocks for Horizontal Bends
- RW-3 – Not Used
- RW-4 – Recycled Water Main Trench Section
- RW-5 – Not Used
- RW-6 – 2" Blow-Off Assembly
- RW-7 – 3/4" & 1" Water Service Lateral for 3/4" & 1" Meters
- RW-8 – 2" Water Service Lateral for 2" or 1-1/2" Meter
- RW-9 – 4" Water Service Lateral for 3" Meter
- RW-10 – 4" Water Service Lateral for 4" Meter
- RW-11 – 6" Water Service Lateral for 6" Meter
- RW-12 – Reduced-Pressure Backflow Device
- RW-13 – Gate Valve
- RW-14 – Not Used
- RW-15 – 1" Air Release and Vacuum Valve Assembly
- RW-16 – 2" Air Release and Vacuum Valve Assembly
- RW-17 – Recycled Water Line Notes
- RW-18 – Recycled Water Sign