



NOTES:

1. THE FINISH GRADE OF THE COVERS SHALL BE FLUSH WITH THE ADJACENT SURFACE.
2. PORTLAND CEMENT CONCRETE (P.C.C.) SHALL BE CLASS A (6 SACKS PER CUBIC YARD AND 3/4" AGGREGATE) WITH 2 LBS. OF LAMPBLACK PER CUBIC YARD OF P.C.C.
3. THE COVER SHALL BE MARKED WITH "SANITARY SEWER".
4. ALL STRUCTURES SHALL BE SET TO GRADE AFTER PAVING.

NAPA SANITATION DISTRICT



TITLE

**TYPICAL METHOD
FOR SETTING
APPURTENANCES**

DATE: MAY 2012

CHECKED BY: MW

APPROVED BY: TH

SCALE: NONE

DRAWING NO.

SS-13