



ONLY ALLOWED WITH SPECIFIC APPROVAL BY THE DISTRICT ENGINEER

**NOTES:**

1. REMOVE FRAME, COVER, TAPER AND BARREL SECTIONS AS REQUIRED TO A MINIMUM OF 3' BELOW FINISHED GRADE.
2. AFTER PLUGGING ALL PIPES IN MANHOLE, THE REMAINING PORTION OF THE BARREL SECTION AND ALL VOIDS CREATED BY THE REMOVAL OF THE UPPER PORTIONS OF THE MANHOLE, SHALL BE BACKFILLED AND COMPACTED TO 90% RELATIVE DENSITY WITH SELF-COMPACTING MATERIAL.
3. BOTTOM OF MANHOLE SHALL BE BROKEN/HOLES CREATED FOR DRAINAGE.
4. CASTINGS SHALL BE DELIVERED TO NAPA SANITATION DISTRICT.

**NAPA SANITATION DISTRICT**



TITLE <b>ABANDONED MANHOLE</b>	DATE: MAY 2012	DRAWING NO.  <b>SS-27</b>
	CHECKED BY: MW	
	APPROVED BY: TH	
	SCALE: NONE	